



**BRIDGE INSPECTION REPORT**

0	0	0	0	0	0	0
---	---	---	---	---	---	---

STRUCTURE FILE NUMBER

OTT  
CO

#3  
ROUTE

0  
UNIT

YEAR BUILT 0

DIST

02

BRIDGE TYPE

231

TYPE OF SERVICE

1 15

SANDUSKY BAY

DECK

5. RAILING: MINOR DENTS AND SMALL HOLE

SUPERSTRUCTURE

10. BEAMS:

LEAKING OVER SIDE (UNDER DRIP STRIP) , THROUGH BEAM JOINTS AND PIER JOINTS

THE CONTINUITY CONCRETE BETWEEN THE BEAMS OVER THE PIERS HAS CRACK UP (SOME PATCHING APPEARS TO HAVE BEEN DONE)

SUBSTRUCTURE

33. ABUTMENTS: WATER LEAKING ON TO SEATS AND DOWN FACE

35. PIERS: HONEY COMB CONCRETE, MINOR CRACKING AND SPALLING (MOST RELATED TO CONSTRUCTION)

WATER IS LEAKING FROM THE SUPERSTRUCTURE ON THE SEATS AND DOWN THE CAP

41. SLOPE PROTECTION: STEEP AND ERODED

CHANNEL

52. PROTECTION: ADD MORE ROCK CHANNEL PROTECTION IN FRONT OF SOUTH PIER

APPROACHES

59. EMBANKMENT: VINES OVER GROWING ENDS OF BRIDGE, GUARDRAIL AND ROAD, PAVEMENT HAS SETTLED BEHIND THE NORTH ABUTMENT CREATING A BUMP FOR SOUTH BOUND TRAFFIC COMING ON TO THE BRIDGE













